# Solar Power Plant and Substation Design Project

IOWA STATE UNIVERSITY and BLACK AND VEATCH

John Jennison, Aayush Shah, Adilene Prieto, Kyle Neal, Logan Miller, Matthew Schindler, Shadoe Rusk

# **Project Vision**

- 60MW Solar Plant and 115kV/34.5kV Distribution Substation
- Black and Veatch
- Those impacted:
  - Surrounding communities
  - Those connected to the grid supplied by this plant
- Benefits:
  - Reduce reliance on fossil fuel/decrease carbon footprint
  - Economic benefits





# Requirements

- 60MW Power Generation
  - Design solar array field for renewable energy production
    - Research into components
    - Voltage Drop Consideration
      - Meets or is below industry max of 3%
    - One-Line, Key Plan, & Grounding Plan
- Cost analysis of design
  - Components
  - Land
  - Labor
  - Solar cost analysis
    - Construction of solar power plant, internal rate of return, solar axis tracking
- Project Management
  - Schedule meetings for Team, Mentor, Client, and TA.
  - Creation of man-hour budgeting and Gantt Chart
    - Defines project timeline expectations
    - Tracks progress of project goals

# **Functional Decomposition/System Architecture**

### 115kV/34.5kV Solar Power Plant

Solar Array Components

- Solar Panel Module
- Rack Layout
- <u>Combiner Box</u>
- <u>PV Skid</u>
  - Inverter
  - Transformer




### **Software Architecture**

	capacity DCB	Strings p Rack		lax lsc for String	String Lengtl	n win	Introduction	nalysis Repor	t				Voltage Drop		
1	DCB#-## DCB1-01 DCB1-02	per rac 2 2	k	Amp 21.75 21.75	feet 137.7 137.7	A	This report discusses the so senior design team. The tea					-	Volt: 3.771 9.761	45	— <mark>7</mark> Degre
	DCB1-03	2		21.75	137.7		complete by mid November						3.549	2762	
		В			С		D	E	F	G	н	1	J	ĸ	1
N	PRODUCT	NUMBER		MANUFAC	TUER	PR	ODUCT NAME	QUANTITY	UNITS	UNIT COST	TOTAL COST				
	JKM410M-5	54HL4		Jinko		410	W Solar Module	187664	each	\$500.00	\$93,832,000.00		Cost of Installation:		
	Box 10-16			Kaco		Co	mbiner Box	273	each	\$500.00	\$136,500.00		Running Sum	\$127,657,17	7.60
	2200 kVA			Schneider		Inv	erter	28	each	\$150,000.00	\$4,200,000.00				
						Wir	e (String) 8 AWG MV	694971.9	foot	\$4.00	\$2,779,887.60			0.0228454	6513
						Wir	e (Jumper) 6 AWG MV	328640	foot	\$4.00	\$1,314,560.00				
						Win	e (Feeder) 600 kcmil MV	53557.5	foot	\$4.00	\$214,230.00				
						Lan	nd	180	Acre	\$1,000.00	\$180,000.00				
						Cor	nstruction Contract	1	each	10,000,000.00	\$10,000,000.00				
						Sub	ostation Contract	1	each	15,000,000.00	\$15,000,000.00				
	DCB2 DCB3 DCB4 DCB5 DCB6 DCB7 DCB8 DCB9 DCB10 DCB10		435.0 435.0 435.0 435.0 435.0 435.0 435.0 261.0 304.5 sum tota combin box curr	0 297 0 249.5 0 202 0 153.5 0 106 0 57.5 0 86 0 82 Il of er	600 600 600 600 600 600 600 600 1MP × 1. AWG si above th		<ol> <li>Other Components Other components in components so far m determined by findin multiplying by the as searches.</li> <li>Outstanding Prices</li> </ol>	nclude combine nake up less th g the total units sumed unit priv are outstandin	er boxes, wi an 2% of th s required fo ce. Unit pric	e total cost. These or the current desig es are based on g	e costs were gn and oogle price		Average of worst-case DCB		2.57% 2.55% 2.53% 2.45% 2.47% 2.45% 1.19% 1.32%
											Array Area			303167.9	085 ft^2
						Provid	ded: Industry standard 1.3				Array Area	(acres)		6.959777	514 acres
											Solar Plant	Total Are	a	8488701.	438 ft^2
			18	76.909(							Solar Plant	Total Are	a (acres)	194.8737	704 acres
			FO	72727:											


# **Conceptual Design**

Curret capacity		Number needed to Perform	Cost		Inverter Load Ratio	Number of rows		Rows per Array
	Combiner Box			Inverter			Racks	
I-V curve		Allowed Current	Inverter Capacity		Number needed to Perform	Racks per row	2	Number of racks removed
Array Design		Array Size	Combiner Box	Inverter	Racks	Organization		Company
En la la companya de	Arrays		Arrays	Array Design	DataSheets		DataSheets	
Racks	an a	Modules	N/A	N/A	N/A	Information on it		Relevancy
			8					




# **Detailed Design Diagram**

#### Our Design



### **Prototype Implementations**



# **Design Complexity**

- Understanding of new concepts
  - Solar array layouts
  - Trench Fill
    - CAB System
  - Grounding Plans
- Growing Market Availability
  - 3 main components -- Product selection analysis (18 total designs)
- Array Efficiency
  - Most conservative use of space
    - Orientation of rack systems
      - Optimization of WxH can greatly reduce ft<sup>2</sup>
      - Tilt
        - Affects Solar Irradiance collected
        - Impacts row spacing
    - Placement of Service Roads
- Cost Analysis
  - Is what we're designing cost effective or costly?
  - Our price estimate: \$127,657,177.60



# **Project Plan - Management Style**

### Waterfall Management Style

- Four main parts
  - Schedule Management
  - Design Report Management
  - Calculations Management
  - Drawings Management.
- Each Team has a Team Lead
  - Team member will be responsible for delegating work
  - Ensuring quality and timeliness for that part of the project.
    - Gantt chart to track our progress throughout the year.
    - Our project documentation is tracked and organized in a shared google drive.
    - We use discord to set meetings, communicate online, and share research.



# **Project Plan - Risks and Mitigation**

Risks	Issues that Arise	Level of Risk	Mitigation
Mis-timing some of the tasks	Causes us to unknowingly fall behind schedule.	Low	Ensure we are on track with the assignments, clear any confusion and We constantly check each other's work with our weekly team, client, advisor and TA meetings.
Miscalculations in one of the parameters	Causes us to deliver incorrect values to our client if this project was executed	Low	We have a large amount of oversight and checks to prevent this.

### **Project Plan - Tools and Requirements**

- Gantt Chart
  - Displayed a good estimate of the amount of time each task will take us.
  - This chart was our guide to aid in the efficiency and accountability of the entire project.
  - Great tool for Black & Veatch to view our progress
- Various programs
  - AutoCad Software
  - Bluebeam Software
  - Microsoft Projects
  - Excel
  - PowerPoint



# **Project Plan - Schedule and Milestones**

### **Project Task Decomposition**

Solar Panel String Sizing Design
Initial Equipment Selection
Array Parameter Tool
Select Solar Panels, Inverters,
Combiner Boxes
Cable List
Conduit List
Deliverable: Design Report


Equipment Sizing Calculation	
Bus Calc	
Grounding Calc	
Lightning Protection	
Ac Calc	
Dc Calc	
Trench Fill	
Cable Tray Fill	
Voltage Drop	
Deliverable: Record Of Calculation	s

Solar Layout Drawings
grounding plan
key plan
Wiring diagram
DC Schematics
Conduit Plan
Equipment Plan
Elevations
Controls Drawing
Lighting Plan
AC Schematics
One lines
Three lines
Bus Plan
Drawing list
Deliverable: Drawing Package

### **Project Plan - Schedule and Milestones**

- Project task decomposition was used to make Gantt chart and man-hour budget
  - Fall Semester: 175 man-hours
  - Spring Semester: 200 man-hours


### **Project Plan - Schedule and Milestones**



### **Test Plan**

- Testing for this project means using quality management to ensure that designs will work as intended
- Review Procedure:
  - 1. Drawings and Calculations reviewed internally by team members
  - 2. Drawings and calculation sent to client and advisor for review
  - 3. Fix errors and incorporate feedback into updated design
- Example: Hand Calculations

V= 1133V SUB ARRAY 267.8A 303.4KW 267.8A 267.8A 363.4KW 303.4KW INV 267.8A 303.41KW 267.8A 267.8A 303.4KW 303.4 KW 160.7A 267.8A 182.1KW 303.4100 187. 5A 267.8A 212.4KW 303.4KM



# Conclusion

- Fall 2021 Schedule
  - In accordance with canvas and our client Black & Veatch we are ahead of schedule
    - Could potentially begin second semester material
    - Client schedule and Finals Week didn't allow for us to start
- Spring 2022 Plan
  - Completed Next semester's gantt chart
  - Plan to start Transformer calculations and design to allow for our solar array to be connected to the grid
  - Re-distribute Individual roles to best suit the team's goal

### **Second Semester Gantt Chart**

	Task Name	Work Duration	
1	Solar Power Plant Design	175 hrs 78 days?	February 2022         March 2022         May 2022           8         11         14         17         20         23         26         29         1         4         7         10         13         16         19         22         25         28         3         6         9         12         15         18         21         24         27         30         2         5         8         11         14         17         20         23         26         29         2         5         8         11         14         17         20         23         26         29         2         5         8         11         14         17         20         23         26         29         2         5         8         11         14         17         20         23         26         29         2         5         8         11         14         17         20         23         26         29         2         5         8         11         14         17         20         23         26         29         2         5         8         11         14         17         20         23
33	EE 491 Canvas Weeklys	94.5 hrs 63 days	
3	Substation Design	200 hrs 116 days?	
4	Substation Planning	60 hrs	
5	Equipment selection	16 hrs 14 days?	
4	Bus Design	8 hrs 7 days	
5	Control House Design	8 hrs 14 days	
6	Conduit List	4 hrs 7 days	
7	Cable List	4 hrs 7 days	
1	Bill of Materials	4 hrs 28 days	
-	Draft Report	16 hrs 28 days	
1	Calculations	62 hrs 105 days?	
	Bus Calc (Tentative)	12 hrs 56 days	
	Grounding Calc	6 hrs 7 days	
1	AC Calc	6 hrs 7 days	
1	DC Calc	6 hrs 7 days	
;	Voltage Drop	6 hrs 7 days	
6	Lightning Protection	6 hrs 7 days	
2	Trenchfill	6 hrs 7 days	<b>*</b>
3	Cable Tray Fill	6 hrs 7 days	*
)	Draft Calculation Report	8 hrs 7 days	
)	Drawings	52 hrs 105 days?	
1	Bus Plan	0 hrs 7 days	
2	Key Plan	14 hrs 7 days	
;	One Lines	6 hrs 14 days	
;	Three Lines	6 hrs 14 days	+
,	Elevations	6 hrs 7 days	+
3	Grounding Plan	6 hrs 7 days	
)	Lighting Plan	6 hrs 7 days	
0	Controls Drawing	6 hrs 21 days	*
1	Drawing List	2 hrs 1 day	
2	Review and Submittal	26 hrs 116 days	
1	All First Drafts Complete	0 hrs 0 days	4/19
2	and a second sec		
2.22		8 hrs 5 days	
4	Review Report Review Calcualtions	8 hrs 5 days 8 hrs 5 days	
3 4 5 6	Review Report		
4 5	Review Report Review Calcualtions	8 hrs 5 days	
	Review Report Review Calcualtions Review Drawing Packege	8 hrs 5 days 8 hrs 4 days	
4 5 6	Review Report Review Calcualtions Review Drawing Packege Merge Documenets and	8 hrs 5 days 8 hrs 4 days	
4 5 6	Review Report Review Calcualtions Review Drawing Packege Merge Documenets and	8 hrs 5 days 8 hrs 4 days	Project Summary Manual Task Start-only C Deadline +
4 5 7	Review Report Review Calcualtions Review Drawing Packege Merge Documenets and Submit t: Project Schedule Fall 20 Split	8 hrs 5 days 8 hrs 4 days	Project Summary I Manual Task Start-only C Deadline
4 5 7	Review Report Review Calcualtions Review Drawing Packege Merge Documenets and Submit	8 hrs 5 days 8 hrs 4 days 2 hrs 1 day	Project Summary I Manual Task Start-only E Deadline IIII Manual Task

### **Contact Us**

**Aayush Shah** Power Engineering Student

ashah01@iastate.edu 630-648-9336

#### **Matthew Schindler**

Electrical Engineering Student

mattsch1@iastate.edu 815-289-2449 **Kyle Neal** *Power Engineering Student* 

kaneal@iastate.edu 224-241-9524

Adilene Prieto Power Engineering Student

aprieto@iastate.edu 712-899-9682

**Logan Miller** *Electrical Engineering Student* 

lwm@iastate.edu 319-538-5804 John Jennison Power Engineering Student

jennison@iastate.edu 319-850-6175

Shadoe Rusk Power Engineering Student

shadoer@iastate.edu 641-831-0789

### References

- "2021 electricity rates by state (updated July 31, 2021)," *Payless Power*, 31-Jul-2021. [Online]. Available: https://paylesspower.com/blog/electric-rates-by-state/. [Accessed: 2021].
- A. Diehl, "Determining module inter-row spacing," *CED Greentech*, Mar-2020. [Online]. Available: https://www.cedgreentech.com/article/determining-module-inter-row-spacing. [Accessed: Sep-2021].
- B. Ludt, "What is a solar tracker, how does it work, and how many types are there?," *Solar Power World*, 16-Jan-2020. [Online]. Available: https://www.solarpowerworldonline.com/2020/01/what-is-a-solar-tracker-and-how-does-it-work/. [Accessed: 2021].
- C. Lane, "What is a solar tracker and is it worth the investment?," *Solar Reviews*, 02-Jan-2021. [Online]. Available: https://www.solarreviews.com/blog/are-solar-axis-trackers-worth-the-additional-investment. [Accessed: 2021].
- "DC-Combiner Box," 2021. [Online]. Available: https://kaco-newenergy.com/index.php?eID=dumpFile&t=f&f=8198&token=abf0049c8de689975ec47671c032d182cfa9c947. [Accessed: 2021].
- "Electricity bills by State Monthly Report: Saveonenergy.com®," *Save On Energy Blog*, 05-Nov-2021. [Online]. Available: https://www.saveonenergy.com/learning-center/post/electricity-bills-by-state/. [Accessed: 2021].
- "New Mexico," *Global Solar Atlas*. [Online]. Available: https://globalsolaratlas.info/detail?c=34.218616%2C-106.026306%2C8&r=USA%3AUSA.32\_1. [Accessed: Sep-2021].
- P. Grana, "What DC to AC inverter load ratio is ideal for your application?," *Solar Power World*, 08-Jul-2016. [Online]. Available: https://www.solarpowerworldonline.com/2016/07/solar-inverters-clipping-dcac-inverter-load-ratio-ideal/. [Accessed: Sep-2021].
- "PV Skid." [Online]. Available: https://solar.schneider-electric.com/wp-content/uploads/2015/06/pv-skid-datasheet-20160826.pdf. [Accessed: 2021].
- "Sunshine & Daylight Hours in Albuquerque, New Mexico, USA," *Sunshine & Daylight Hours in Albuquerque, New Mexico, Usa Sunlight, Cloud & Day length.* [Online]. Available: http://www.albuquerque.climatemps.com/sunlight.php#:~:text=There%20is%20an%20average%20of,sunny%2078.9%25%20of%20daylight%20hour s. [Accessed: 2021].
- "Tiger Pro 54HC 395-415 Watt Mono-Facial Module," 2020. [Online]. Available: https://jinkosolarcdn.shwebspace.com/uploads/JKM395-415M-54HL4-(V)-EN-F2.1.pdf. [Accessed: 2021].